

REQUEST FOR PROPOSAL | CONSTRUCTION SERVICES

Request for Proposal

PROJECT INFORMATION

Owner	Targa Delaware LLC
Bid Expiration Date	8/20/2026
Project	Zia Hills Extension
PipeID(s) (where appl.)	DEL-JC
FacilityID(s) (where appl.)	N/A
County(ies) & State(s)	Lea County, New Mexico / Loving County, Texas
Coordinates (where appl.)	N/A
Agreement Effective Date*	8/15/2026
Substantial Completion Date*	8/28/2026
Final Completion Date*	9/28/2026

* Preliminary dates are provided for bidding purposes only; once executed, the Project-specific Agreement shall govern the Effective Date, Guaranteed Substantial Completion Date, and Guaranteed Final Completion Date. Bidders shall independently develop their own Project schedule and, at their discretion, may specify an accelerated substantial completion/final completion date in their proposal, so long as they are adequately resourced to achieve those dates safely and in compliance with Project Specifications.

Additional Anticipated Milestone Dates

Equipment Tag(s) & Description	Ready-to-Ship Date
WeldFit Launcher	8/17/2026
WeldFit Receiver	8/17/2026
30" Valves /A&B Valve	8/15/2026
Question Due Date	August 11th, 2026, at 7:30 pm

“Owner” submits this request-for-proposal (RFP) to the Contractor (“Bidder”) for construction services of the Project listed above. Bidders are responsible for their own interpretation of all information listed below; Owner is not responsible for the accuracy or completeness of the information or Bidder’s interpretation.

Reference the Scope of Work sections below for additional Project information.

PROPOSAL INSTRUCTIONS

Bidding Contacts & Due Date

Owner Representative(s) & Email(s)	Tommy Sheppard – tsheppard@targaresouces.com Jason Bordayo – jbordayo@targaresouces.com
Bid Due Date & Time (CT)	August 16th, 2026, at 7:30 pm

REQUEST FOR PROPOSAL | CONSTRUCTION SERVICES

Acknowledgement of Intent to Bid

The Contractor shall promptly acknowledge its intent to bid on this RFP by sending an email to the Owner Representative(s) listed above. The Contractor is advised that proposals may be requested from both union and non-union/open shop contractors.

Pre-Bid Meeting

Pre-Bid Meeting Date & Time	August 12th, 2026, at 7:30 pm
Location/Address	Lea County, New Mexico / Loving County, Texas/Online

Attendance at the pre-bid meeting is required unless otherwise stated by the Owner Representative(s); not attending shall not relieve the Contractor's responsibility to properly estimate the difficulties and cost of successfully performing the scope of work (SOW). The submittal of a proposal is considered evidence that the Contractor has inspected the Site and is sufficiently aware of all the conditions that may affect the Work. The Contractor's proposal shall be priced to accommodate these conditions, even when such conditions are not explicitly referred to in the SOW or obvious from the Site visit.

Where held at a location with an office, attendees are required to check in at the office prior to entrance to Site. Personal protective Equipment required includes the following: Fire retardant clothing (FRC), hard hats, steel toed boots, and safety glasses.

Proposal Preparation

The preparation of a proposal shall be by and at the expense of the Contractor. Owner will not be responsible for any costs or expenses in preparing and/or submitting Contractor's proposals; attendance at meetings during the bid process; participation in teleconferences or interviews; or in providing any supplemental information.

The Contractor is responsible for examining the complete RFP, Attachments, Exhibits, Clarifications, and Addenda, and for establishing all conditions that may affect the cost or performance of the Work. Failure to do so is at the sole risk of the Contractor, who is deemed to have included all costs for performance of the Work in its proposal, and no relief can be given for errors or omissions by the Contractor.

The Contractor shall promptly notify the Owner Representative(s) should it find:

- Discrepancies in (or omissions from) the RFP
- Ambiguous meaning or intent in the RFP
- Any other questions arising from the RFP

The Contractor may not submit questions to the Owner less than three (3) business days before the bid proposal due date. The Owner's reply to such notices may be in the form of supplementary correspondence or, as appropriate, by a formal Addendum to the RFP, but in either case, such replies will be issued simultaneously to all Contractors. The Owner may, by such Exhibits, Clarifications, and Addenda, modify any provision or part of the RFP at any time prior to the bid closing date and time. The Contractor shall acknowledge receipt of all Clarifications and Addenda in its bid proposal submission letter.

The Owner will not be bound by – and Contractor must not rely on – any oral interpretations or clarifications of the RFP documents.

Proposal Guidelines

Proposals shall be based on the information provided in the SOW, including any changes to the SOW by Owner's issuance of Addenda. Proposals not complying with this document– or partial/incomplete proposals – may not be considered. Unless noted

REQUEST FOR PROPOSAL | CONSTRUCTION SERVICES

otherwise in Appendix A.5, the Contractor shall submit an electronic copy of its proposal to the Owner Representative(s) listed above prior to the bid due date and time identified above.

- The submission of a proposal indicates acceptance by the Contractor of all conditions contained herein, notwithstanding any exceptions listed by the Contractor.
- All exceptions to (and deviations from) the SOW documents shall be established in the Contractor's proposal.
- Proposals shall include the full legal name and business address of the Contractor (including its street address if it differs from its mailing address).
- Proposal shall be signed and dated by an individual with signature authority on behalf of the Contractor.
- Proposals by joint ventures, consortia, associations, or partnerships shall designate one participant to represent all those forming the bidding entity.
- The Owner Representative(s) listed above are the Contractors points of contact for all communications, whether technical or commercial in nature, throughout the entire bid period from the time the Contractor receives the RFP through the selection of a successful Contractor (if any). The Contractor shall submit all questions/clarifications concerning the RFP to these persons via email. Once the Agreement is fully executed, the points of contact for all communications shall be as specified on the Agreement.
- The intent of the proposal request is to capture **all** costs required for safe, compliant, and complete installation of pipelines, well connects, and/or facilities, including: excavation, hot tie-ins, supports, preparation for service, fencing, coating, grading, demolition, materials handling, and cleanup. If the Contractor identifies tasks that are required but are not captured by the quantities and rates on the bid form, the Contractor shall notify Owner at the time of proposal submittal and provide an associated unit or lump sum cost for each task.

Pricing

All pricing, stated in U.S. Dollars, must be in accordance with the Bid Form in this RFP.

- Pricing shall include all costs to the Contractor for materials, labor, consumables, Equipment, testing, and all items of expense, fees, taxes, duties, overhead, and profit for Contractor's complete performance of the SOW.
- The Owner reserves the right to request, and have the Contractor furnish, any accounting breakdown of all prices submitted. This request may also be made of the successful Contractor after the Contract Price has been finalized.
- In the case of any discrepancy between words and figures, the words shall prevail. In the case of errors in addition or extension, the unit prices quoted shall prevail.
- If Contractor submits a proposal as a partnership or joint venture, only unified sums, rates, prices, or conditions will be accepted. Sums, rates, prices, or any conditions which differ between individual parties of a partnership or joint venture will not be accepted.

Proposal Checklist

Contractor proposals shall include:

- 1) Contractor Proposal, including:
 - o Cover letter on Contractor letterhead, signed by authorized individual (including printed name and title)
 - o Assumptions, Clarifications, and Exclusions
 - o List of proposed Subcontractors
- 2) Completed Bid Form in **native Excel format**
- 3) Project Schedule & Manpower Loading Chart (excl. Continuing Contractor RFP's)
 - o Demonstrates that the Contractor can comply with the Substantial and Final Completion Dates
 - o Includes the sequence of Work and any interim milestones necessary to achieve the Work timely

REQUEST FOR PROPOSAL | CONSTRUCTION SERVICES

- If awarded, the Contractor shall use this Project schedule/sequence of Work to further develop its detailed schedule and work execution plan
- 4) Project Organization Chart
 - Proposed Contractor team members, including project manager, construction superintendent, discipline foremen, and Subcontractor superintendents (when applicable)
 - The Contractor shall identify its representative who shall be the primary point of contact (POC) for Contractor and Owner on all aspects of the Work.
 - Proposed field and home office organization charts that indicate key positions
 - Resumes for key personnel, highlighting relevant experience on similar projects
 - Proposed candidates shall be available for interview as part of the bid evaluation
 - Resumes for key personnel may also be required for proposed Subcontractors, at Owner's discretion
- 5) Execution Strategy (excl. Continuing Contractor RFP's)
 - If awarded, the Contractor shall use as basis of work execution plan
- 6) Rate Sheets
 - Contractor and Subcontractor (personnel, Equipment, & tools)
- 7) Internal safety resources relevant to the Project, including on-Site and off-Site personnel and their training/qualifications

Project Award

The Owner reserves the right to accept other than the lowest cost proposal and to accept or reject any proposal in whole or in part, or to reject all proposals with or without reason, and if no proposal is accepted, to abandon the Work, to self-perform such Work, or to have the Work performed in such other manner as Owner may elect.

If a Project is awarded, unit rate costs shall be fixed, regardless of final actual unit quantities. If the Contractor is awarded the Project, the only deviations recognized will be those mutually agreed upon and incorporated into the Agreement in writing.


The award of this Project shall be contingent upon the Bidder successfully executing an Owner's Master Service Agreement (MSA) and compliance with Owner's safety and insurance requirements. If an MSA is not in place prior to awarding Work, bids may not be considered. If an MSA is needed, Contractors may submit a formal MSA request by contacting the Owner Representative(s) listed above. Terms within the MSA (or Construction Contract, where applicable) will govern the Work.

The Contractor must define all materials (not provided by Owner) to be purchased that cannot be obtained within thirty (30) days after Agreement execution.



ZIA HILLS EXTENSION

Scope of Work | Construction Services



SCOPE OF WORK | CONSTRUCTION SERVICES

A.0 - Scope of Work

The Contractor shall complete all Work identified in this **Attachment B Scope of Work** document per the attached, referenced, and incorporated Drawings and specifications and in strict accordance with the Construction Agreement to which this Scope of Work is attached (the “Agreement”). All capitalized terms used but not defined herein shall have the same meaning given them in the Agreement. The Contractor shall provide all supervision, labor, utilities, services, Equipment, consumables, and materials (unless expressly noted otherwise herein) required to complete the Work.

Any deviations or conflicts to these requirements shall be submitted to the Owner for review and approval prior to performing the Work. If no clarifications or deviations are requested, it is assumed the Contractor intends to and will comply with all requirements in the SOW.

SAFETY

Owner seeks partnerships with Contractors whose essential priority is ensuring everyone, everywhere, every day goes home safe. Contractor and Contractor’s Subcontractors must meet Owner’s safety standards.

Contractor must comply with Owner’s “Take 10!” program – which emphasizes (a) utilizing procedures, (b) hazard identification, (c) having an emergency plan in place, (d) discussing the task as a team, and (e) using stop work authority where appropriate – to complete each task safely.

Additionally, the requirements below are to complement and augment Contractor safe work policies. Costs associated with complying with these programs are included in the Contract Price.

Stop Work Obligation

If any Contractor feels they are involved in or witnessing an unsafe act, they have an obligation to stop all relevant Site Work immediately. Work may not be permitted to resume without local safety coordinator and Owner project manager permission. No one will be reprimanded for employing the stop work obligation – rather, use of this policy is strongly encouraged.

Personnel Protection Equipment (PPE)

The Contractor is required to equip their employees and their Subcontractors with the Equipment below and enforce the following PPE requirements for the duration of the Project:

- Steel-Toed Boots
- Safety Glasses
- Hard Hats
- Reflective Vests
- Fire Retardant Clothing (as required)
- Ice Cleats (when icy conditions are present)
- Hearing Protection (as required)
- 4 gas LEL Monitors (in live facilities)
- H₂S Monitors (in areas with elevated levels of H₂S)

SCOPE OF WORK | CONSTRUCTION SERVICES

Additionally, when performing work in facilities with elevated levels of H₂S, the Contractor must comply with OSHA 1910.134 by providing, being fit-tested, and wearing OSHA- or NIOSH-approved respiratory protection and providing medical certifications *before* engaging in applicable operations.

ISNetworld (ISN) Contractor Vetting

ISN reviews Contractor safety performance – including fatalities, TRIR, history, HSE questionnaires, OSHA citations, EMR, and written safety programs – and provides Owner with a summary scorecard. The Contractor shall furnish a list of all Subcontractors that will be utilized; Owner may elect to perform an ISN review to ensure Subcontractors have adequate grades.

Tailgate Meetings, Work Permits, and Job Safety Analyses (JSA's)

When performing Work at existing (brownfield) locations, the Contractor shall obtain daily safe work permits (SWP's) from an Owner Representative (or designee) each day Work is performed.

Regardless of Site location (brownfield or greenfield), the Contractor shall conduct documented daily “tailgate meetings” and coordinate with Owner on-Site personnel daily to ensure Work is performed in safe and workmanlike manner. Job hazard assessments (JSA's) are also required for each task that a Contractor performs; the Contractor shall turnover copies of each JSA to on-Site inspection daily.

- JSA's must be filled out OR reviewed at the location of the task.
- Each identified job or task must have a JSA conducted prior to beginning the Work. Review the JSA with all affected personnel. If at any time the daily job tasks, hazards, or conditions change, the Work will be stopped and a new JSA will be required.
- The work crews must keep the JSA readily available for audit at the Site until the job is completed or rescheduled for another time. Any new workers that come onto the Site must review and sign onto the JSA.
- Owner personnel and representatives may routinely inspect Work within their area to ensure that all Work is conducted in accordance with safe work requirements.

Targa Contractor Safety Manual

The Targa Contractor Safety Manual identifies uniform ES&H requirements designed to ensure that Contractor safety orientation, coordination, and safety administration practices are communicated to and understood by its employees. The Contractor shall comply with all Owner safety requirements as outlined in Targa's Contractor Safety Manual.

Baseline & Ongoing Safety Orientations

All Contractor employees and Subcontractors are required to attend Owner's region-specific safety orientation prior to performing Work on an Owner's location; this safety orientation may occur at Site or at the regional field office, at Owner's discretion. The Contractor shall comply with regional-specific safety policies that are provided prior to or alongside mobilization.

Contractor shall provide a site safety orientation to each direct & subcontracted employee prior to performing Work On-Site.

Substance Abuse

SCOPE OF WORK | CONSTRUCTION SERVICES

All Contractor and Subcontractor employees shall comply with Owner's substance abuse policy. Compliance may include a urine analysis test of each employee prior to their admission into the workplace. All costs are to be included in the Contract Price.

Special Circumstances

Project-Specific Procedures

In special circumstances – such as the COVID-19 pandemic – Owner may request the Contractor to supply unique, Project-specific procedures for Owner review. Work practices shall always abide by applicable CDC, federal, state, tribal, and local guidelines.

Fatigue

Reference Owner's fatigue guideline, intended to ensure personnel have the energy and focus required to complete every task safely, timely, and of a high quality.

Cold Weather

Reference Owner's cold weather guideline, intended to ensure personnel are not performing Work in unsafe climates.

Lock Out-Tag Out

Unless otherwise specified, the Contractor is responsible for temporary blinds and skillets; for facility tie-ins, the Contractor is also responsible for furnishing the purge gas (e.g. Nitrogen). Contractor and Owner are responsible for jointly drafting an electrical/mechanical isolation plan for each hot tie-in, including: lock points, disconnection points, blind points, purge points, and purge medium. Each plan shall be submitted at least one (1) week prior to tie-in; Owner's construction representative and operations representative will review and approve each energy isolation plan.

Spotters & Lifting

Lifting Equipment, Equipment operating in reverse, and moving Equipment underneath power lines shall have a designated "spotter" overseeing the Work.

When responsible for lifting equipment, the Contractor shall provide all necessary Equipment for safe lifting, including qualified operators and riggers. For critical lifts (e.g. LACT's, compressors, etc.), the Contractor shall complete and provide a lift plan to be reviewed & signed by Owner Representative (or qualified designee).

Excavation

The Contractor is responsible for complying with all "One Call" rules and regulations. The Contractor will ensure that a qualified and competent person will be locating all buried foreign lines and utilities.

Fire Watch

A dedicated and trained fire watch – equipped with (2) 30-pound extinguishers – is required while working within 35' of a potential ignition source. Additionally, the Contractor shall supply a water truck adequate for fire suppression (200-gal or more) if dry conditions are present at the time of construction.

Social Media & Internet Posting

Contractor should not permit its employees to use Social Media during work hours, and further should not permit any activities on Social Media that relate in any way to or comment on Targa's business, employees, customers or

SCOPE OF WORK | CONSTRUCTION SERVICES

competitors. Contractors and their employees may not create social network accounts, postings, webpages, or blogs that appear to be affiliated with or endorsed by Targa or that violate any law, regulation, or Targa policy. Further, Contractors and their employees are not authorized to speak on behalf of Targa or to represent that they do so in any social media websites without written approval by Targa executive management.

Contractors and their employees should also never post any financial, confidential, sensitive, or proprietary information relating to Targa, including incidents involving safety or otherwise engage in discussions that may be offensive and damaging to the individual and/or Targa.

Cell Phones

Cell phones and headphones are prohibited on-Site except for emergencies and supervisors engaged in company business.

DESIGN CODES & STANDARDS

Contractor acknowledges receipt of copies of Owner's construction standards, suite of construction forms, and standard typical Drawings as issued by Targa Resources LLC or its Affiliates ("Targa"), which are available via the Targa E&C Portal link below, and such are incorporated into this Scope of Work by reference for all purposes:

<https://targa.sharepoint.com/sites/trengportal>

Contact the Owner Representative(s) to request access to this portal.

All fabrication, construction, and testing performed by the Contractor shall conform to the latest edition of all Applicable Codes and Standards, Specifications, and all codes and standards referenced therein – and other requirements which are part of this Scope of Work and in effect at the time of the Effective Date, including but not limited to:

- Owner Standards
 - Electrical
 - Electrical Construction Standard
 - Electrical Area Classification Guideline
 - Foundations
 - Foundations Standards and Specifications
 - Hot Tap Standards & Procedures (where applicable)
 - In-Service Welding and Hot Tap Standards and Procedures for Steel
 - Saddle Fusion and Hot Tap Standards for Poly Pipe
 - Hydrostatic and Pneumatic Testing
 - Hydrostatic and Pneumatic Testing Standards and Procedures
 - Insulation
 - Insulation Standards and Specifications
 - Fire Systems and Fire Protection
 - Materials
 - Approved Manufacturers List (AML)
 - Painting & Coating
 - Painting & Coating Standard
 - Pipelines (where applicable)

SCOPE OF WORK | CONSTRUCTION SERVICES

- Land Pipeline Construction Specifications
 - Poly Pipe Design, Installation, and Testing
- Safety
 - Contractor Safety Manual
- Spacing
 - Spacing Guidelines Matrix
- Welding Standards & Procedures
 - Owner Welding Manuals
 - Owner WPS & PQR
- Industry Standards
 - American Concrete Institute (ACI)
 - 318 Building Code Requirements for Structural Concrete
 - 301 Specification for Structural Concrete
 - American Petroleum Institute (API)
 - Piping, fitting, and valve standards
 - RP 500 Classification of Locations for Electrical Installations
 - American Society of Mechanical Engineers (ASME)
 - Pipeline, piping, fitting, and valve standards
 - Vessel standards
 - American Society for Testing and Materials (ASTM)
 - D698 Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort
 - D1557 Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort [56,000 ft-lbf/ft³ (2,700 kN-m/m³)]
 - American Welding Society (AWS)
 - D1.1 Structural Welding – Steel
 - Code of Federal Regulations (CFR)
 - Title 29, Part 1926, Occupational Safety and Health Act (OSHA) Rules and Regulations
 - Environmental Protection Agency (EPA) Standards
 - International Society of Automation (ISA)
 - 5.1 Instrumentation Symbols and Identifications
 - National Electric Manufacturers Association (NEMA)
 - VE-2-2006 Cable Tray Installation Guideline
 - National Electrical Safety Code (NESC)
 - International Electrical Testing Association (NETA)
 - ATS & MTS Standards
 - National Fire Protection Association (NFPA)
 - 70 National Electric Code
 - 70E Standard for Electrical Safety in the Workplace
 - Uniform Building Code (UBC)
 - Underwriters Laboratories (UL) Standards
 - All applicable local, state, tribal, and federal rules and regulations, including local building codes

Additionally, for B31.3 projects:

SCOPE OF WORK | CONSTRUCTION SERVICES

- ASME Section IX Qualification of Material Joining Processes
- Owner B31.3 PVF Specs
- Owner General Plant Design Standards & Specifications

Additionally, for B31.4 projects:

- API Std 1104 Welding of Pipelines and Related Facilities
- ASME B31.4 Pipeline Transportation Systems for Liquid Hydrocarbons and Other Liquids
- Owner General Liquids Pipeline Design Specs and Standards (B31.4)
- Owner B31.4 PVF Specs

Additionally, for B31.8 projects:

- API Std 1104 Welding of Pipelines and Related Facilities
- ASME B31.8 Gas Transmission & Distribution Piping Systems
- Owner General Field Gas Pipeline Design Specs and Standards (B31.8)
- Owner B31.8 PVF Specs

Additionally, for 49 CFR 192-jurisdictional projects:

- Title 49 CFR Part 192 Transportation of Natural and Other Gas by Pipeline
 - o In case of conflict between ASME B31.8 & Title 49 CFR Part 192, Title 49 CFR Part 192 shall take precedence

Additionally, for 49 CFR 195-jurisdictional projects:

- Title 49 CFR Part 195 Transportation of Hazardous Liquids by Pipeline
 - o In case of conflict between ASME B31.4 & Title 49 CFR Part 195, Title 49 CFR Part 195 shall take precedence

Additionally, for gas plant, terminal, fractionation, and NGL pump station projects:

- API RP 550 Manual of Installation of Refinery Instruments and Control Systems

Additionally, for Texas projects:

- Standards of the Texas Commission on Environmental Quality (TCEQ)

Tasks Requiring Operator Qualifications (OQ's)

N/A

SCHEDULE

The Contractor shall staff the Project sufficiently to achieve the Project Schedule by working six (6) Days per week, ten (10) hours per Day. If applicable, the Contractor's baseline schedule shall account for traditional non-working holidays that occur during the Project, including New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Day after Thanksgiving, and Christmas Day.

The Owner will not reimburse any costs incurred by the Contractor – including overtime, holiday work, and working seven (7) Days per week – to meet the Project Schedule. The Contractor shall make every effort – beginning with additional staffing/supervision – to meet the Project Schedule, while maintaining compliance with

SCOPE OF WORK | CONSTRUCTION SERVICES

Owner's fatigue and cold weather guidelines. Deviations from the Project Schedule must be approved via a Change Order in accordance with the Agreement.

The Contractor will not be reimbursed for Days of no work or reduced productivity resulting from weather. Whenever possible, the Contractor is encouraged to utilize local shop fabrication for off-Site fab to minimize weather impacts.

Additional Project Schedule Clarifications
Pipe Available Approximately 10/15/2025
Kickoff & Weekly Meeting Clarifications
Prior to mobilization, the Contractor shall participate in a kick-off meeting (remote or in-person as designated by Owner). Additionally, the Contractor shall participate in weekly interface and coordination meetings. Weekly meetings shall be focused on progress of the Work, schedule of activities, and identifying areas needing resolution between parties. The meetings shall focus on activities where the performance is ongoing or anticipated to start or where concerns have arisen.

Construction Metrics

The Contractor shall provide factual, accurate, and complete information with respect to the Work already performed, the Work in progress, the Work scheduled, and the events affecting the performance of the Work. Weekly Progress Reports are due within 24 hours prior to the scheduled weekly meeting. Contractor-provided Weekly Progress Reports shall include:

- Safety Issues, Trends, and Focuses from the past Week and for the coming Week
- Project Statistics, both Work and commercial-related (e.g. safety data incl. manhours & recordables, milestone/unit quantities percent complete, etc.)
- Updated Project Schedule & Weekly Manpower Loading (historical actuals and forecast)
- Summary of Work Completed in Prior Week
- Summary of Work to be Completed in Following 2 Weeks
- RFI & Change Order Logs
- Construction Pictures

The Contractor shall track the following metrics and make data available to on-Site inspection/Owner Representative(s) upon request. The Contractor shall also track all unit quantities associated with unit rates (e.g. helical piles, extra fence gaps, sandbags, etc.). Progress on these metrics shall be captured on the Contractor Weekly Progress Reports. The awarded Contractor shall supply estimated-at-completion (EAC) quantities for each of these metrics prior to mobilization.

- For pipeline projects:
 - o Clearing / Grading (lf)
 - o Stringing – ML Pipe (lf)
 - o Stringing – Bore Pipe (lf)
 - o Bend & Setup (lf)
 - o Line Welding (lf)
 - o NDE (lf)
 - o Field Joint Coating (lf)
 - o Trenching (lf)
 - o Lower-In (lf)
 - o Backfill (lf)
 - o Tie-Ins (lf)
 - o Final Cleanup (lf)
 - o Revegetation (lf)
 - o Bore & HDD Adder (lf)
- o Additionally, if the following are included as separate unit rate invoiced items:

SCOPE OF WORK | CONSTRUCTION SERVICES

- HDD/Bore Pre-Test Adder (lf)
 - Rock Bore Adder (lf)
 - Wireline Adder (lf)
 - Rock Blasting (lf)
 - Line & Bore Pipe Transportation Adder (lf)
- For facility projects:
 - Mechanical
 - Concrete poured (yd)
 - Helical piles installed (ea)
 - Structural steel installed (tons)
 - Pre-NDE circumferential inches welded (in)
 - Post-NDE circumferential inches welded (in)
 - Insulation (lf)
 - Major Equipment Set (ea)
 - Electrical
 - Duct Bank Installed (lf)
 - Cable Tray Installed (lf)
 - Grounding Installed (lf)
 - Above Ground Conduit Installed (lf)
 - Control/Communication Wire Pulled (lf)
 - E.G. 300' of three-conductor cable would be reported as 300', not 900'
 - 120V – 277V (Power) Wire Pulled (lf)
 - 480V (Power) Wire Pulled (lf)
 - 4160V+ (Power) Wire Pulled (lf)
 - Terminations (ea)
 - Heat Trace Installed (lf)
 - I/O Ready for Service (ea), also known as Loop Checks

MOBILIZATION & DEMOBILIZATION

Construction of a particular item shall not begin until its Drawing(s) have been issued-for-construction (IFC'd) or otherwise approved by the Owner.

The Contract Price shall include all costs to mobilize to and demobilize from the Project Site. ***Unless mobilization and demobilization costs are explicitly identified as extra costs in the Calculation of Contract Price, these costs shall be embedded in other unit rate/lump sum items identified in the Calculation of Contract Price (e.g. base lay).***

- Mobilization scope includes the movement of all Equipment, Contractor-furnished materials, and material storage trailers to the Site; transporting and training of personnel; permits; and labor & Equipment needed to setup the Project Site. Unless otherwise noted, the Contractor is required for obtaining temporary (construction) power for its Equipment and operations.
 - The Contractor shall furnish office trailers, temporary office trailer power, and porta johns for their employees and Subcontractors. The Contractor shall furnish bottled drinking water for all on-Site Contractor and Subcontractor employees.

SCOPE OF WORK | CONSTRUCTION SERVICES

- The Contractor shall furnish internet and wireless network access for all on-Site Contractor, Subcontractor, and Owner employees from mobilization through demobilization.
- If Owner elects to furnish an office trailer, the Contractor shall provide space for Owner to set its office trailer.
- The Contractor shall remove all Equipment, excess or unused Contractor-furnished materials, storage trailers, personnel, etc., that were brought to execute the Project. The Contractor shall restore the Site, Material Staging Location(s) (where applicable), and all temporary staging locations to their preexisting conditions. As part of demobilization, all construction-related payments due to landowners, government entities, utility providers are the responsibility of the Contractor and shall be paid in full prior to Final Completion.

MATERIALS

Owner-Provided Materials

Unless otherwise noted herein, the Owner will only provide materials marked as 'By Owner' below:

Materials	By Owner	By Contractor
Mainline & bore pipe and fittings (for pipeline projects)	X	
LACT's and Gas Meters	X	
Materials, other than Small Bore PVF, identified in the Project Bill of Material (BOM)	X	
Materials in attached equipment & instrument schedules, unless otherwise designated therein	X	
Small Bore PVF ¹	X	

All other materials and consumables required to execute the Project shall be furnished by the Contractor.

For pipeline projects, the Contractor shall provide 1-Week advance written notification to inspection and the Owner Representative(s) prior to needing mainline and bore pipe delivered.

Contractor will verify every line on the bill of material prior to accepting the material. Within three (3) Days of receipt and prior to utilization of material, the Contractor shall acknowledge, in writing, that material is in good condition, is provided in the correct quantities/sizes, and is provided with MTR's & packing slips. Contractors shall not accept material without MTR's unless approved otherwise by an Owner Representative in writing.

¹ If Small Bore PVF is marked as 'By Contractor' above, Owner-provided materials include pipe/valves/fittings **2" and larger**, excluding bolts and gaskets. In this case, pipe/valves/fittings smaller than 2" shall be furnished by the Contractor. Bolts and gaskets – including those requiring replacements after hydrotest – shall be furnished by Contractor. A BOM may be provided to assist Contractor with estimating bolt/gasket/small-bore PVF quantities, but this BOM is intended for information and estimation-purposes only and Contractor is responsible for verifying quantities and incorporating a reasonable contingency in the Contract Price.

SCOPE OF WORK | CONSTRUCTION SERVICES

Contractor is required to provide 1-Week notice of needing additional material to Owner Representative(s); the Contractor is responsible for picking this material up from Owner's designated location. Change Orders associated with this material transportation will not be approved.

The Following Owner-Provided Material and Equipment will be Delivered Directly to Site

WeldFit Launcher and Receiver / Induction Bends

Note the following regarding Owner-furnished equipment (e.g. vessels, compressors, process skids, specialized electrical equipment, prefabricated pig traps, LACT's, gas meter buildings, etc.) deliveries:

- The Owner will provide the Contractor with vendor & transportation contact information for Owner-provided materials delivered directly to location. The Contractor is responsible for coordinating directly with the transportation agency to deliver these materials to-Site, keeping Owner Representative(s) apprised of all updates.
- Unless otherwise specified, the Contractor is responsible for coordinating and offloading all materials at Site. Unless otherwise approved in writing, materials must be offloaded the same Day as their arrival, so long as they arrive to Site 4:00p or earlier (local time).
- As the Contractor is directly communicating with the transportation agency, the Owner is not responsible for any offloading standby charges, so long as the transportation agency provides a minimum 24-hour notice of their arrival date and arrives within a reasonable tolerance of their estimated arrival time.
- If foundations are not ready prior to equipment delivery, the Contractor will need to temporarily set equipment on-Site and relocate it to its permanent location once its foundation is ready.

Excess Materials

Prior to Final Completion, the Contractor shall provide 48-hour notice to Owner Representative(s) of all excess material. Upon approval, the Contractor shall load, transport, and offload all excess material at Owner's designated warehouse location. Prior to offloading, the Contractor shall submit a completed material return form, including material heat numbers, descriptions, and AFE/PO info.

Contractor-Provided Materials

The Contractor is responsible for providing all consumables, including welding rods, oxygen, acetylene, propane, nitrogen (Excl. nitrogen for pipeline purge), temporary supports, wood working mats, digging mats, temporary fencing/posts, etc. Where responsible for installation, the Contractor is responsible for furnishing piles, pipeline coating, shoring or trench boxes, skids, Cad-weld kits (w/rubber boot), cement/concrete, foam, scoria/caliche/rock/gravel, geotextile fabric, paint, hay bales, silt fencing, tape and dope, etc.

Material Handling

Once Contractor is in possession of Owner-provided material, the Contractor is responsible for proper storage and security of this material and management of all MTR's & packing slips; all misplaced or stolen material shall be replaced expeditiously by the Contractor at its sole expense. Warehousing shall be furnished for sensitive equipment, including electronic materials that need to be protected from the weather and secured. The warehouses (trailers, conex boxes, etc.) shall remain locked when not in use.

All open-ended materials shall be night-capped at the end of each shift with acceptable materials to prevent intrusion of snow, ice, trash, soil, wildlife, etc. The Contractor shall ensure that all welds are capped prior to leaving the jobsite for the day. Welds left incomplete overnight will not be accepted.

SCOPE OF WORK | CONSTRUCTION SERVICES

Offsite Material Staging Locations (Where Applicable)

Material Staging Location(s)	Line Pipe will be staged Monahans Bulk Transfer Yard 3377 TX-18, Thorntonville, Tx 79756 .625 and .750WT Bore Pipe will be at Falcon Laydown Yard 31.9879924,-104.0621470
-------------------------------------	--

If the Contractor chooses to secure a staging yard separate from the Material Staging Location listed above, it shall do so at the Contractor's expense. All materials for this Project shall be located at Owner's Material Staging Location specified herein unless otherwise noted as being delivered directly to the Project Site or Contractor's yard (if any); the Contractor is responsible for transportation to Project Site.

- The Contractor shall provide all labor and Equipment required to load or unload all materials at the Material Staging Location and/or Project Site as designated by Owner, including but not limited to those materials supplied by the Contractor, Subcontractor(s), and Owner. The Contractor shall supply all dunnage and padding material necessary for loading pipe to protect coating.
- The Contractor shall return all surplus materials to the location(s) designated by Owner.
- The Material Staging Location will be jointly utilized by Contractor and Owner personnel and equipment for the duration of the Project. The Contractor shall make no additional claim for compensation or time due to delays needed to avoid interference with Owner's operations at the Material Staging Location.

Additional Material Handling Clarifications

The Contractor shall employ an on-Site material handling and receiving person that will be responsible for receipt, inventory, storage and material tracking of all Contractor, Subcontractor, and Owner-provided materials. Upon Owner's request, the Contractor's material handling and receiving personnel shall provide all current inventory and material tracking information. The Contractor shall install temporary fencing in their staging yards (if any). Site access will be provided by the Contractor when workers are present and secure the Site when workers are not present.

MISCELLANEOUS

On-Site Coordination

Unless otherwise noted, Survey, and 3rd party Inspection will be contracted separately by the Owner. The Contractor shall provide 72-hour written notice to inspection when requiring these services.

The Contractor shall cooperate and make reasonable accommodations in their construction activities to facilitate all other Owner-employed contractors and Owner employees, including, as applicable, inspection, survey, permanent fencing, facility mechanical, pipeline, electrical, programming, insulation, painting, commissioning, cranes, utilities, and IT/SCADA/communications.

Welding Qualifications

All welders shall be tested or provide documentation showing they have been tested to the approved and applicable Owner welding procedure within the last six (6) Months. Otherwise, the Owner shall provide WQ inspection and test pipe; welder testing shall take place at a local location designated by the Owner. The Contractor shall bear all other costs for certifying welders.

Owner's Welder Qualification Scope

SCOPE OF WORK | CONSTRUCTION SERVICES

Owner will oversee and manage welder testing and mobilize WQ inspection, as req'd, up to (4) times throughout the Project.

Sandblasting, Priming, & Painting

Excluding items below, all above-ground piping, valves, and structural supports shall be sandblasted, primed, and coated per Owner Specifications:

- Stainless steel materials
- Control tubing
- Actuators
- OEM Painted Equipment (engines, compressors, motors, pumps, electrical enclosures)
- Valve Handles
- Control Valves
- Bolting, Studs, & Nuts

Owner-supplied mechanical, electrical, and controls equipment are delivered painted unless otherwise noted; the Contractor is responsible for any touch-up painting associated with this equipment.

Paint Color
BLM – Shale Green (Munsell Soil Color No. 54 4/2) / All Other – Targa White
Structural Steel Support Color (or Galvanized)
Galvanized
Platforms, Ladders, Stairs Color (or Galvanized)
Erecta Step
Handrails, Stair Tread Lips, Railings, & Toe Guards Color
Safety Yellow
Insulation Tin Color
N/A
Pipe Clamps Color (or Galvanized)
Galvanized

Cleanliness

The Contractor will always be required to maintain a minimum of one enclosed trash bin and one securely anchored sanitary facility on the Site. Trash bins and sanitary facilities shall be emptied and/or cleaned regularly as needed. All garbage, trash, and debris at the Site and staging area shall be collected and placed into a Contractor-provided trash container. The container shall be removed and transported to a disposal facility by the Contractor.

Littering will not be tolerated. The Contractor shall, at all times, keep the Site, Material Staging Location, and Contractor work yard(s), if any, free from accumulations of waste materials and rubbish, shall keep weeds and other vegetation cut and shall maintain stored materials and equipment in a manner that will avoid risk of damage to materials or become a hazard to personnel, equipment, materials, or the Site.

The Contractor is responsible for fines levied for failure to comply with this provision (or landowner stipulations regarding trash pickup).

Punch-List & Warranty

SCOPE OF WORK | CONSTRUCTION SERVICES

The Owner will document Punchlist tasks for items that have not been completed to Owner's satisfaction during construction. The Contractor is responsible for completing all Punchlist items to Owner's satisfaction.

Warranty terms are as defined in the Agreement.

COMMERCIAL & CHANGE MANAGEMENT

The Contractor shall identify a single point of contact for the duration of the Project for contractual matters, and such "Contractor Representative" shall be specified in the Agreement. Likewise, Owner will identify "Owner Representative" point of contact(s) for the duration of the Project for reviewing and processing cost and/or schedule Change Orders, and such representative(s) shall be specified in the Agreement.

Where used, unit quantities listed in the Agreement's Calculation of Contract Price establish the approved quantity of Work for the Project – any Work exceeding these unit quantities **MUST** be approved in writing by the Owner Representative(s) prior to starting Work. Any Work not covered by the lump sum and/or unit pricing on the Calculation of Contract Price **MUST** be submitted for approval in writing using the Owner Change Order Form. For these changes, the Contractor must receive approval in writing by the Owner Representative(s) prior to starting Work.

The Contractor **will not be compensated** for any Work performed without prior written approval by the Owner Representative(s). Contractor will only be paid for actual quantities installed. A deductive change order may be issued by Owner at Final Completion to the extent actual quantities are less than those listed on the Calculation of Contract Price.

Any change in schedule – even those with no cost impact – that impacts meeting the following milestone dates **MUST** be submitted for approval in writing and approved via a Change Order:

- 1) Site Mobilization date per Project Schedule
- 2) Substantial Completion Date
- 3) Final Completion Date

Requests for Information

The Contractor shall submit questions or requests for additional information (RFI's) to the Owner Representative(s) and designee(s) using the Owner's Request for Information form. The Owner shall be consulted regarding any inconsistencies between construction Drawings.

Incorporated Documents & Attachments

Contractor acknowledges that the following documents and attachments have been provided to Contractor and are incorporated into this Scope of Work by reference for all Purposes:

Description	Drawing No.	Revision	Date
Launcher to Tie-In		3	6/25/2024
30in Trap Bypass		1	8/11/2025
MLBV with Future		A	6/03/2025
Riser		A	6/06/2025
30" Launcher/Receiver Concrete Pier Layout		A	6/19/2024
Zia Hills Extension All Deflections			3/28/2025

SCOPE OF WORK | CONSTRUCTION SERVICES

Description	Drawing No.	Revision	Date
Zia hills Pipeline Crossings			3/28/2025
Zia Hills Hydrotest Forms			8/8/2025
NDT Scope of Work			
BLM Land Guidelines	Form 2800-14		August 1985
New Mexico State Land Office Best Practices for Surface Users	Exhibit A		8/12/2025
Clear to Construct Line List			8/12/2025
Weld Fit – Skid Mounted Bi-Directional	SLB-RH-3036-57634-V3-SMU	0	7/16/2025
Targa 2 WPS & PQR	Targa 2	1	10/10/2017
Targa 5 WPS & PQR	Targa 5	12	7/16/2024
KMZ			8/12/2025
Alignment Sheets	65671-ZHEX		8/12/2025

SCOPE OF WORK | CONSTRUCTION SERVICES

A.1 | Pipeline Work Clarifications

PIPELINE SUMMARY

Service (e.g. LP Gas, IP Gas, HP Gas, Residue Gas, Natural Gas Liquids, Crude Oil, Produced Water)
Sour Gas
Line Pipe NPS, Wall Thickness, Grade, Seam Type, Joint Length (SRL/DRL/TRL/QRL), and Metallurgy
30", .594, X-60, HSAW, QRL, API 5L PSL2
Bore Pipe NPS, Wall Thickness, Grade, Seam Type, Joint Length (SRL/DRL/TRL), and Metallurgy
30", .594, X-60, HSAW, DRL, API 5L PSL2 for Bores on cross lines and lease roads
30", .625, X-65, HSAW, QRL, API 5L PSL2 for bore at 287+01 – 293.21
30", .725, X-65, HSAW, QRL, API 5L PSL2 For bore at 889+92 – 892+92
Approximate Base Lay Length (')
136,165
Upstream Start Point (Station 0 + 00)
0+00
Downstream End Point and Station (X + XX)
1361+65
Applicable Piping Code (B31.4/8)
B31.8
Jurisdictional (Regulatory) Applicability
N/A
Temporary & Permanent Workspace (')
New Mexico 80' (50' Permanent / 30' Temporary) / Texas 30' Permanent and Temporary varies depending on Landowner

Pipeline Cover Requirements

Normal Excavation (')
4'
Consolidated Rock (')
3'

Project-Specific Scope & Clarifications
See Land Restrictions/Pipe will be staged Monahans Bulk Transfer Yard 3377 TX-18, Thorntonville, Tx 79756

ROW

Contractor shall always stay on the ROW. Unless otherwise noted, the Contractor shall plan on accessing the ROW only via existing roads that intersect the pipeline ROW.

Contractor shall make their own inquiries to verify the existence and location of all foreign pipelines and utility crossings. The amount, depth, location, and number of pipeline and utility crossings are not necessarily known to Owner.

Areas of archaeological and paleontological significance may be encountered along the route of the pipeline. Pursuant to landowner right-of-way stipulations, archaeological and paleontological surveying and/or monitoring of the right-of-way may be

SCOPE OF WORK | CONSTRUCTION SERVICES

conducted by Owner-contracted consultants. The Contractor shall coordinate and make allowances in their right-of-way and pipeline construction to ensure Permit-compliant archaeological and paleontological monitoring is completed (monitoring, sampling, and analysis will be provided or contracted separately by Owner). Typical archaeological and paleontological monitoring shall be completed, in identified archaeological areas, on trench walls and bottoms/spoil piles during construction.

Landowner Provisions

The Contract Price includes landowner provisions established in the Project line list. The line list includes requirements from the landowners that Owner's easement(s) cross; these requirements have been legally negotiated and agreed upon between landowner and Owner. Any fines or penalties caused by Contractor's non-compliance of these provisions will be borne by the Contractor. The Contract Price shall include and account for all requirements contained in this provision, **except** those directly applicable to revegetation, which is covered by the reseeding/fertilizing unit rates.

The Contractor shall comply with excavation requirements of Owner and foreign utility owners. If a utility crossing is subject to an intercompany Permit or agreement, the Contractor shall comply with all provisions in the utility crossing Permit or agreement. Crossing depths shown on alignment sheets shall be considered minimums; additional depth may be required to comply with Owner and foreign utility owner requirements.

Survey

Initial centerline staking and construction boundary staking will be provided by Owner at adequate intervals to facilitate and ensure the Contractor's pipe placement is accurate with the permitted pipeline location. The Contractor will be responsible for maintaining the original pipeline centerline. The Contractor will be responsible for all offset staking. Offset staking will be required by Owner in all areas of construction.

The minimum offset for new lines paralleling existing lines shall be specified by Owner on a Project-specific basis.

CLARIFICATIONS

Where applicable, unit items described below shall be constructed in accordance with Owner's standard typical Drawings. The Contractor shall not perform tasks below in excess of approved quantities defined by the Agreement (as an example, the Contractor shall obtain written Owner Representative approval prior to completing a fourth Extra Fence Gap if the current Agreement only includes three Extra Fence Gaps).

A.1.1 Base Lay

For avoidance of doubt, any scope items that are not explicitly identified as an adder are part of base lay. Base lay includes – but is not limited to – labor and Equipment required to complete the tasks described below (e.g. mobilization, fencing, clearing, trenching, etc.)

- One (1) Mobilization and one (1) Demobilization (unless otherwise indicated in the Calculation of Contract Price)
- Safety Fencing and Temporary 5-Wire Fencing
 - o Includes furnishing and installing temporary safety and/or 5-wire fence as designated by Owner inspection, including around the perimeter of all open bell holes and potholes at the end of each workday and as stipulated by the line list/landowner requirements.
 - o Includes fence gaps (at locations where existing fence requires being cut) that are identified on the Project-specific alignment sheets and line list (landowner requirements). Fence gaps include furnishing and installing access gates per standard typical Drawings; when requested, the Contractor shall repair fence to its original condition upon Final Completion.

SCOPE OF WORK | CONSTRUCTION SERVICES

- Clearing, Scraping, and Grading
 - o All activities required for clearing, stockpiling, burning, burying, chipping, mulching, spreading of brush and timber, and gapping fences during construction.
 - o Includes hauling of brush and timber when specified on the construction line list.
 - o All activities required for grading, providing traffic control, installing/improving access roads; preparing a level working surface for heavy construction Equipment; and performing topsoil separation.
 - o The Contractor shall handle trees and revegetation in accordance with the construction line list.
- Bridges
- Dust Control
- Trenching / Ditching
 - o All activities required for excavating the pipe trench for the top of the pipe to be buried to the specified depth including excavating, shoring, sheet piling, bell holes, tie-ins, and trench dewatering. Ditching, including rock trenching, is included in this line item. All rock encountered is included in this task **except** for areas of rock requiring blasting. Rock trenching, as included in this task, shall include:
 - Machinery, labor, and Equipment required to excavate rock
 - Machinery and labor for rock removal and disposal
 - Equipment and labor necessary for segregation of rock for padding
 - o Unless otherwise noted, the Contractor shall maintain a minimum of 24" of clearance between the proposed pipelines and any foreign lines that are crossed throughout the pipeline route. The Contractor shall not excavate any ditch within 10' of a fence or roadway until the pipeline is ready to be laid in the particular fence or roadway crossing without Owner Representative approval.
 - o Includes double ditch where specified in the line list/landowner requirements.
 - o Includes foam trench breakers (plugs) identified on alignment sheets; trench breakers shall be of foam construction – not sand bag construction – unless otherwise specified by Owner.
 - o In the event that conditions of the ditch are determined by Owner to be unacceptable for backfilling or installing pipe, due to – but not limited to – debris, ditch sloughing, snow, or water accumulation, the ditch will be cleaned at the Contractor's expense.
- Offloading & Stringing
 - o All activities required to offload pipe from stringing trucks and distribution of the various pipe joints along the right of way, immediately adjacent to the ditch or ditch line. This process shall include handling and hauling of materials; vacuum pipe lifter to offload pipe from stringing trucks and setting on right of way. Wooden timber skids used during stringing shall be provided by the Contractor. The Contractor shall ensure the correct piping is strung on the right-of-way based on the alignment sheets (wall thickness, grade, coating, etc.)
- Field Bending and Cutting of Segmentable Fittings
 - o All field bends shall be in accordance with Owner's Specifications; unless otherwise noted, all other PI's shall be segmentable fittings or induction bends.
- Welding
 - o Includes labor and Equipment for handling, cutting, grinding, internal mechanical transitioning, beveling, aligning (with lineup clamps) and welding of the pipe.
 - o Includes installation of bends & fittings (incl. ells, tees, and wyes)
 - o Includes standby for X-Ray/survey/hydrovac
- Coating
 - o All activities required for pre-jeeping and jeeping prior to backfill; coating of pipeline including applying approved coating to all field joints, tie-ins, and transitions; and repairs to existing piping.

SCOPE OF WORK | CONSTRUCTION SERVICES

- Includes coating of below-grade fittings (ells, tees, and wyes)
- Lower-In / Tie-Ins
 - All activities required for lifting the pipe and carefully lowering the welded sections into the ditch, preparing trench bottom, and all tie-ins including final tie-ins. This item also includes procuring and utilizing concrete set-on weights / saddle bags as identified on alignment sheets.
 - All foreign materials shall be removed prior to lowering in pipe or backfilling the pipe trench.
 - Includes all foreign line crossings – including labor, Equipment, supply, placement, and removal of associated laminated mats – as well as associated CP test stations/appurtenances and zinc ribbon/appurtenances identified on alignment sheets or contained in Scope documents. *Includes all foreign line/utility crossings that have an outer diameter of 4.5" or less, regardless of whether these lines/utilities are identified on alignment sheets/Scope documents.* Additional detail regarding foreign line crossings may be found below in its unit rate definition.
 - Includes all open-cut dirt, gravel, asphalt, and concrete road crossings – regardless of whether they are identified on alignment sheets or contained in Scope documents – including installation of ARO pipe, fill, and associated trench breakers and restoration of roads to pre-construction conditions. If required, extra fill dirt, gravel, or trench breakers may be invoiced on a unit rate basis *only* for road crossings *not* identified on alignment sheets/Scope documents.
 - When requested, the Contractor shall provide a unit rate adder for zinc ribbon footage not shown on the alignment sheets.
- Backfill / Padding
 - All activities required for refilling all areas trenched and/or excavated during construction with either original backfill or pad dirt and installing yellow warning tape when required.
 - Includes padding bucket/machine where required.
- Pressure Testing
 - Contractor shall complete hydrostatic pressure test(s) of the installed pipeline and associated facilities.
 - Pressure tests shall include a sizing plate run (ran either before or after pressure testing, at the Company's election). The Contractor shall record the minimum I.D. of each bend, tee, wye, and elbow prior to installation; when running a sizing plate, the Contractor shall furnish a sizing plate with O.D. equal to 90% - 95% of the lowest I.D. component in the pipeline (pipe or fitting). Unless otherwise specified by the Company, sizing plates shall be run prior to tying in permanent pig traps.
 - The Contractor shall supply all documentation, records, and reports related to sizing plate runs, hydrotesting, cleaning, drying, as applicable.
 - All activities required for pressure testing, dewatering, and drying the new pipe or appurtenances including: procuring, hauling, and **offsite** disposing of hydrotest water unless otherwise noted below; performing internal cleaning, internal pressure testing, dewatering and drying to Owner construction standards; anomaly digs and repairs resulting from tool run data reporting defect(s) outside of Owner's acceptance criteria (incl. hydrovac and supply, placement, and removal of mats); and installing, removing, and cleaning up required dewatering structures.

For gas projects that contain piping segments of multiple Class Locations, more than one hydrostatic test may be required. As an example, a Project that contains both Class 3 segment(s) and Class 1 segment(s) may require separate hydrostatic tests, as the minimum hydrostatic test pressure in a Class 3 location is different than that of a Class 1 location. In these cases, the Contractor's base lay cost shall include all costs related to performing these different hydrostatic tests. Reference the table, below, for Project-specific information:

SCOPE OF WORK | CONSTRUCTION SERVICES

Project-Specific Hydrostatic Test Info	N/A
--	-----

Hydrotest medium shall be furnished, hauled, and disposed of as follows:

Test Medium (Water, Water/Glycol, N2)	Water
Furnished By (Owner/Contractor)	Contractor
Source Location	Contractor
Hauling By (Owner/Contractor)	Contractor
Disposal By (Owner/Contractor)	Contractor
Disposal Location	Contractor

- Includes all test manifolds, pumps, piping, blinds, skilllets, weld caps, temporary barrels, frac tanks, fittings, traps, air compressors, generators, light plants, and all other Equipment necessary for hydrostatic testing; cleaning, drying, running tools and digging/repairing anomalies as required by plans, Specifications, and Owner or designated Owner Representative(s).
 - Drying requirements apply to both pipeline and facility components; the Contractor is responsible for drying fabricated assemblies and facility piping to the same Specifications as the pipeline(s).
- Unless otherwise noted, includes providing adequate lengths of contingency piping in test for all final tie-in points.
- Testing shall comply with the following sequence:
 - If applicable, pre-clean with spool pieces installed at mainline valve locations (mainline valves out)
 - Remove spool pieces and install mainline valves
 - Fill with water and perform hydrotest per Owner Specifications. The Contractor shall provide procedure for Owner's approval prior to commencing Work.
- Where required, for Texas projects, the Contractor shall have the completed hydrotest report signed and stamped by an engineer licensed in the state of Texas confirming a successful test, in accordance with all applicable regulatory requirements.
- Post-Construction Quality Assessments
 - Contractor shall be responsible for excavating, investigating, repairing, and backfilling any anomalies identified as part of post-construction assessments, including:
 - Caliper Tool/ILI/MFL runs
 - Direct Current Voltage Gradient (DCVG), Alternating Current Voltage Gradient (ACVG), and/or other coating assessment technologies
 - DCVG and/or ACVG surveys will be contracted separately by Owner
- Clean-Up
 - The Contractor shall provide all labor, Equipment, and materials required to furnish and install CP test stations *in addition* to those otherwise required per this Scope document to maintain a *maximum* distance between test stations of 1 mile. Cathodic protection test stations shall be installed per standard typical Drawings.
 - All activities required for the clean-up and restoration of the Site(s) to their original condition. Scope includes removing and disposing of large rocks 4" and larger where required by landowner (other than those associated with solid rock excavation by blasting); rock picking; chisel plowing; windrowing; final grading; repaving; restoring access roads and parking lots; stoning; fencing; closing gaps and installing 16' gates; installing slope breakers, terraces, water bars, pipeline markers, and aerial markers; and compliance with landowner requirements.

SCOPE OF WORK | CONSTRUCTION SERVICES

- Frozen chunks of dirt shall not be used in the reclamation process. Ground disturbed by construction activities shall be graded to original shape and contours. All shaping and contouring shall be completed in a manner to match pre-construction contours and require approval of Owner or Owners Representative, governing agency, and in compliance with landowner requirements.
- Pipeline markers shall be installed along the right-of-way at locations indicated on the alignment sheets; if the alignment sheets do not include pipeline marker locations, base lay scope shall include the markers listed below. Pipeline signs will be provided by the Owner but furnishing the post and hardware and installation of the complete pipeline markers is by the Contractor.
 - The Contractor is responsible for line-locating the buried lines to ensure pipeline markers are installed directly above the pipelines.
 - Unless noted on the alignment sheets, pipeline markers shall be installed on:
 - Both sides of roads and creeks
 - Alongside fence lines
 - At PI's
 - And to ensure they are always in line-of-sight (e.g. as someone is standing at a particular pipeline marker, they should be able to see a pipeline marker in each direction along the pipeline route).
 - When crossing cultivated fields, pipeline markers should only be installed at field breaks and field edges.
- Data Deliverables
 - As part of its Scope of Work, data listed below shall be provided in hardcopy form **prior to** Substantial Completion and PSSR/PSSRNC and, within three (3) Weeks following the PSSR/PSSRNC (but no later than Final Completion), the Contractor shall also submit the data listed below electronically.

Document	By Contractor	By Others or N/A
Contractor Status Reports	X	
Change Order Forms & Log	X	
RFI Forms & Log	X	
Substantial Completion Documentation	X	
Lien Waivers & Final Payment Release Documentation ²	X	
Contractor-Obtained Construction Permits	X	
Hydrotest Water/De-Water Permits & Required Lab Data	X	
Packing Slips/Delivery Tickets for Contractor-Received Material	X	
Weld & Heat Maps		X
Welder Qualification Test Records		X
Welder Qualification Logs		X
Welding Inspection Reports		X
Welding Compliance Reports		X
Hydrotest Plans/Forms	X	X

² May be furnished after Substantial Completion but must be provided prior to Final Completion

SCOPE OF WORK | CONSTRUCTION SERVICES

Document	By Contractor	By Others or N/A
Hydrotest Test Charts, Calibration Certificates, & Disposal Data	X	
Dewater and Drying Results	X	
Tie-In Forms		X
Hot Tap Forms & Procedures		X
Coating & Jeeping Summary Reports		X
Coating Blast Profile Forms		X
Torque Reports		X
Sizing Plate Results	X	
Caliper Tool/ILI/MFL Results	X	
Anomaly Repair Forms		X
Line Crossing Forms		X
Potholing Excavation Forms		X
OQ – Covered Task Lists (for jurisdictional projects)	X	
OQ – Supporting Documentation (for jurisdictional projects)	X	
Punchlist ³	X	
Joining Qualification Records (for poly projects)	X	
JSA's & Safe Work Permits	X	
One-Calls	X	

- Additional Base Lay Inclusions
 - o Items marked as 'Part of Base Lay Rate' below shall also be included in the Contractor's base lay rate.
 - o Tasks in the table below are further defined later in this document.

Task	Part of Base Lay Rate	Separate Unit Rate	By Others
Non-Destructive Examination (NDE) ⁴		X	
Caliper Tool Run ⁵		X	
Sandbags		X	
Rock Blasting		X	
Silt Fence		X	
Wattles		X	
Hay Mulch/Curlex		X	
Fertilizer		X	

³ May be furnished after Substantial Completion but must be provided prior to Final Completion

⁴ If NDE is marked as 'Part of Base Lay Rate', all welds shall be x-rayed. Realtime NDE is required for all welds, except that conventional x-ray may be utilized for tie-in welds; film shall be digitized and submitted to Owner. Technician Qualifications/Certifications and NDE Procedures shall be provided to Owner for documentation. Owner may elect to have an auditor on-site to review and approve or reject all x-rays (Note: Owner's decision shall be final). Contractor shall deliver digital x-rays and reader sheets to Owner's Designated Auditor daily.

⁵ The Contractor is responsible for assisting with caliper, ILI, and/or MFL tool runs in instances where Owner elects to contract a 3rd party to complete these tool runs.

SCOPE OF WORK | CONSTRUCTION SERVICES

Task	Part of Base Lay Rate	Separate Unit Rate	By Others
Reseeding		X	
<u>Extra</u> Foreign Pipeline Crossings		X	
<u>Extra</u> Double Ditch		X	
<u>Extra</u> Foam Trench Breakers		X	
<u>Extra</u> River Weights		X	
<u>Extra</u> Hydrovac		X	
<u>Extra</u> Laminated Mats		X	
<u>Extra</u> Rock Shield		X	
Line & Bore Pipe Transportation to ROW		X	

Base lay footage is calculated as follows:

- Includes entire pipeline length (linear foot), including the length of bores and HDD's, based on as-built survey footage.
- Excludes above-ground fabrication; base lay footage ends at the elbow where the riser/MLV originates, inclusive of on-pad below-grade piping.

A.1.2 Bores & Horizontal Directional Drills (HDD) Adder

Invoiced **in addition to** base lay footage. Includes – but is not limited to – labor and Equipment required to complete the following tasks: Site preparation, ingress/egress to drill Site, board matting, excavation of bore pits on entry/exit, handling and disposal of drill mud and cuttings, mud motor (if required), rock boring equipment (if required), and furnishing material & installation of associated cathodic protection components (test stations, anodes, etc.). If drills are lengthened or added for Contractor convenience, no additional compensation will be approved; moreover, lengthening a drill or adding a drill for Contractor convenience requires prior Owner Representative approval, as Owner still incurs higher material costs for additional ARO bore pipe.

HDD/Bore quantity encompasses tie-in point to tie-in point, **not** point of entry to exit. Unless otherwise noted, the Contractor shall assume there is no additional temporary workspace for bores.

If separate unit rates are provided for HDD and conventional bores, only bores explicitly identified as HDD on the Project alignment sheets shall be invoiced using the HDD rate unless otherwise approved by Owner Representative.

Bore & HDD cathodic protection components shall be per the standard typical Drawing.

A.1.3 HDD/Bore Pre-Test Adder

HDD/Bore piping runs shall be pre-hydrotested for four (4) hours where specified by Owner Specifications and when requested by the Owner Representative(s). All costs associated with this hydrotest scope shall be included in the HDD/Bore pre-test adder unit rate, including furnishing and off-Site disposal of hydrotest water.

A.1.4 Wireline Adder

Invoiced **in addition to** base lay footage and the applicable bore adder above. Includes all labor and Equipment required to furnish wireline services by a qualified and competent crew approved by Owner. The Contractor shall obtain Owner Representative approval prior to mobilizing wireline Equipment.

A.1.5 Split-Tee Hot Tap – In-Service Pipeline (Hot Tie-In)

SCOPE OF WORK | CONSTRUCTION SERVICES

Includes labor, Equipment, and mechanical excavation required to prepare existing pipeline for hot tapping. Unless otherwise noted, the size referenced in the Scope of Work refers to the mainline pipe diameter (e.g. the diameter of the existing pipeline being tapped). Contractor shall complete the in-service split tee welding and installation per Owner's hot tap procedure. Additionally, the scope includes one (1) dedicated 16-hour crew and Equipment shifts per 8" and smaller hot tap and two (2) dedicated 16-hour crew and Equipment shifts per 10" and larger hot tap.

Hot Tap Fitting & Specialty Hot Tap Crew Scope Responsibility (if appl.)

N/A

A.1.6 Electrofusion Saddle Installation – In-Service Pipeline (Hot Tie-In)

Includes labor, Equipment, and mechanical excavation required to prepare existing pipeline for hot tapping. Unless otherwise noted, the size referenced in the Scope of Work refers to the mainline pipe diameter (e.g. the diameter of the existing pipeline being tapped). Contractor shall complete the in-service electrofusion saddle installation and complete the hot tap per Owner's procedure. Unless otherwise specified, the Owner will supply the hot tap fitting.

A.1.7 Barred Tee & Piggable Wye – In-Service Pipeline (Hot Tie-In)

Includes labor, Equipment, and mechanical excavation required to prepare existing pipeline for cutting and tee tie-in. Unless otherwise noted, the size referenced in the Scope of Work refers to the mainline pipe diameter (e.g. the diameter of the existing pipeline being tied into). Includes one (1) dedicated 16-hour crew and Equipment shift per tie-in. Includes installation and fabrication of below-grade barred tee. Excludes N2 supply, vac truck/frac tanks, and hydrovac, which shall be supplied separately by the Owner unless otherwise specified.

A.1.8 Pig Traps

Fabrication

If the Owner is unable to provide prefabricated pig traps, the Owner will supply pipe/valves/fittings and skid material to the Contractor and the Contractor shall complete all fabrication scope according to Owner-supplied trap Drawings. If Owner provides pre-fabricated pig traps, the Contractor is responsible for verifying all trap components are properly tightened and torqued and shall only invoice quoted 'installation' costs.

Installation

Foundation Type

Concrete

The Contractor is responsible for installing & furnishing the foundation above and setting pig traps. Where utilized, helical piles associated with pig trap installations shall be invoiced separately per their quoted unit rate. Horizontal trap pricing shall also exclude the cost of the riser set, which shall be invoiced separately. Where applicable, for vertical pig traps, installation scope includes furnishing/installing a below-grade riser block and setting an Owner-provided access platform (incl. furnishing/installing two (2) curb stops and wedge anchors). Installation scope includes coating.

Note that some newer pig trap designs must be recessed up to 1' below-grade (e.g. the structural steel skid base sits below finished grade) – this is required to maintain the same center-of-pipe trap elevation as the gas meter building(s) and/or riser. In these cases, the Contractor is responsible for this excavation Work, installing the recessed piles, and backfilling the skid with gravel after the trap is set.

A.1.9/10 Riser and Mainline Valve Sets (MLV)

SCOPE OF WORK | CONSTRUCTION SERVICES

Fabrication

The Owner will supply pipe/valves/fittings and, if identified by the standard typical Drawings, adjustable pipe supports to the Contractor and the Contractor shall complete all fabrication scope according to Owner-supplied riser/MLV Drawings.

Installation

Includes all labor, Equipment, and excavation required to install a riser or mainline valve set according to the provided standard typical Drawings. Includes material (concrete/foam) and labor required to install the riser support block(s). Includes installation and fabrication of below-grade barred tees or piggable wyes/wye block for new pipelines. Includes rock shield for riser and wye blocks as shown on the standard typical Drawings. Where applicable, installation scope includes setting an Owner-provided access platform and furnishing/installing two (2) curb stops and wedge anchors. Installation scope includes coating. Where utilized, helical piles associated with riser and MLV installations shall be invoiced separately per their quoted unit rate.

A.1.11 Above-Ground Site Preparation & Finishing

Includes all labor, materials, and Equipment to complete Site prep (including cut/fill) and achieve desired minimum compaction (of 95% of standard proctor unless otherwise specified); final grading; final cover and Site cleanup; furnish & install signage and signage posts per standard typical Drawings; and furnish & install fencing and gates per Project-specific details.

A.1.12 Demolition (when applicable)

Includes labor, Equipment, and excavation required to complete the Project-specific demolition scope. Includes removal/disposal of existing concrete piers (to at least 6" below final grade) and existing helical piles that are no longer required. After LOTO is completed, Contractor shall decommission, drain, cut, remove, clean, and transport demo'd pipe, fittings, etc., including below-grade proving lines. Where required, the Owner shall contract vac truck services for removal and transportation of fluids. After removal of below-grade piping is completed, the Contractor shall backfill and return the Site to a condition equal to or better than its pre-existing state.

Prior to disposal of material, the Contractor shall notify the Owner of the material that is slated for disposal for review and approval. Unless otherwise specified or earmarked by the Owner, demolition scope includes disposal of all demo'd components. Disposal shall be in accordance with all state and local requirements, inclusive of applicable NORM testing and cleaning requirements.

For materials that the Owner elects to retain, the Contractor shall transport and offload these materials at a designated local Owner facility.

A.1.13 Helical Piles

Includes all labor, Equipment, materials, and fabrication required to complete installation of helical piles per standard typical Drawings. The Contractor shall furnish torque reports that indicate piles provide specified strength.

A.1.14 Sandbags

Includes furnishing and installing sandbags.

A.1.15 Rock Blasting

Includes all labor and Equipment required to excavate and ditch through rock **only when** blasting is required. The Contractor shall obtain Owner Representative approval prior to mobilizing rock blasting Equipment.

A.1.16 Silt Fence

SCOPE OF WORK | CONSTRUCTION SERVICES

Includes furnishing of silt fence and all labor and Equipment required to install silt fence. Scope includes daily monitoring through to reseeding (or demobilization if reseeding cannot be performed until warm weather returns) and maintenance of silt fence. The Contractor is responsible for removing silt fence when 70% of vegetation regrowth has occurred or 2-years after re-seeding has been performed, whichever is earlier.

A.1.17 Wattles

Includes furnishing of wattles and all labor and Equipment required to install wattles. The Contractor is responsible for removing wattles when 70% of vegetation regrowth has occurred or 2-years after re-seeding has been performed, whichever is earlier.

A.1.18 Hay Mulch/Curlex

Includes furnishing and all labor and Equipment required to install hay mulch/curlex when directed by the Owner Representative(s) or per the line list.

A.1.19 Fertilizing

Includes furnishing and installation of fertilizer per the construction line list.

A.1.20 Reseeding

Includes furnishing and planting of seed per the construction line list. Includes furnishing and installation of water bars.

A.1.21 Hydrotesting of Miscellaneous Spool Adder

The Contractor shall supply a lump sum cost to complete hydrotesting of a miscellaneous pipe spool separate from pipeline testing, where approved by the Owner Representative(s). All costs associated with this hydrotest scope shall be included in the rate, including furnishing/disposing hydrotest water.

A.1.22 Move Arounds (Per Crew & Full Spread)

Only applicable when Contractor is required to relocate its crew and transport its Equipment to a different location on the ROW because of Owner's inability to obtain permits or landowner permissions at cost and terms reasonably acceptable to Owner. Does not apply to instances where the Contractor is responsible for moving their Equipment and personnel. The Contractor shall obtain Owner Representative approval prior to performing a move around.

A.1.23 Standby (Per Crew & Full Spread)

Only applicable when the Owner is at fault for causing the Contractor to standby for a full day of no productivity. Does not apply for instances where the Contractor, government agencies, landowners, or weather is responsible for preventing Work from taking place. Formal notice that the Owner may incur standby charges must be issued in writing by noon on the day that standby is occurring. Standby invoices must be accompanied with T&M tickets, submitted no later than (24) hours after the standby occurred and signed by an Owner Representative. These tickets may not include overtime charges. When approved, the Owner will pay the lesser of the applicable T&M rates or the quoted standby unit rate.

A.1.24 Extra Foreign Pipeline Crossings (Open-Cut)

Includes all labor; Equipment; supply, placement, and removal of laminated mats; excavation of bell holes and associated hydrovac water, Equipment, labor, and disposal; welding; tie-ins; cuts and bevels; bending; coating; material & installation of foreign line test stations; and backfill. The Contractor shall maintain a minimum 24" clearance between new and existing pipelines unless otherwise noted or required by the utility being crossed; the foreign pipeline crossing unit rate will not be adjusted if additional crossing depth is required to satisfy the utility's requirements. Only foreign pipelines that satisfy **ALL** the following criteria are eligible for incremental unit rate invoicing:

- Pipelines (above and below grade) with an outer diameter exceeding 4.5"

SCOPE OF WORK | CONSTRUCTION SERVICES

- Pipelines are discovered during construction, are not identified on alignment sheets, and are not within 20' of a pipeline already identified in the alignment sheets.

This unit rate **excludes** HDD/bore crossings, pipelines with outer diameters of 4.5" or less, and pipeline crossings identified on alignment sheets or other documents contained within the Scope of Work. When open-cut, a grouping of two or more foreign pipelines in a contiguous 20' stretch is considered one (1) foreign pipeline crossing.

Foreign line test station materials & installation shall be per the standard typical Drawing.

A.1.25 Extra Fence Gaps

Excludes fence gaps identified on alignment sheets and/or the line list.

Includes all labor and Equipment to furnish and install additional access gates per standard typical Drawings; when requested, the Contractor shall repair fence to its original condition prior to Final Completion.

A.1.26 Extra Double Ditch

Excludes double ditch identified on the line list/landowner stipulations, which is included in the base lay scope.

Includes all additional labor and Equipment to complete double ditching. Double ditching performed for Contractor convenience shall not be invoiced. Contractor shall obtain Owner Representative(s) approval prior to double ditching.

A.1.27 Extra Foam Trench Breakers

Excludes foam trench breakers (plugs) identified on alignment sheets (covered in base lay) and associated with road crossings identified in alignment sheets/Scope documents.

Includes all labor and Equipment to furnish and install additional foam trench plugs per standard typical Drawings. Trench breakers shall be of foam construction – not sandbag construction – unless otherwise specified by Owner.

A.1.28 Extra River Weights

Excludes weights/saddle bags identified on alignment sheets, which are included in the base lay scope.

Includes all labor and Equipment to furnish additional high-density aggregate gravel-filled permeable geotextile sacks that are designed to either set-on or strap-on and straddle the pipeline to achieve buoyancy control.

A.1.29 Extra Hydrovac

Hydrovac services are included in the base lay rate (for known foreign line crossings) and in the foreign line crossing rate (for incremental foreign line crossings identified during construction). Additional hydrovac services – required when potholing for positive line identification when installing a new parallel line in an existing pipeline corridor, for example – shall be invoiced using the quoted day cost and actual full days worked; standby/mechanical issues/weather days shall not be invoiced and will not be approved. Hydrovac work not associated with foreign line crossings must be approved by the Owner Representative(s) prior to mobilizing hydrovac personnel and Equipment.

Any other labor or materials associated with hydrovac work – including supervision and coordination – shall be included in the base lay unit price. Hydrovac mud may be spread on ROW if allowed by the landowner; otherwise, it must be transported to a location specified by the Owner at the pre-job meeting. The hydrovac day rate shall include all water costs.

Hydrovac unit rates shall include furnishing and installing additional dirt for backfill, as required.

SCOPE OF WORK | CONSTRUCTION SERVICES

A.1.30 Extra Laminated Mats (Access Only)

Excludes laminated mats required for bore crossings, HDD crossings, and foreign pipeline crossings, which are included in their respective rates.

Includes furnishing of mats and all labor and Equipment required to set laminated mats required for access. Mats shall be free of residue when set. Scope includes maintenance of mats and cleaning of any residue/trash remaining from mats prior to Final Completion. Contractor is responsible for repairing/replacing damaged mats and for removing laminated mats prior to Final Completion.

During the RFP process, the Contractor shall review and familiarize themselves with the route, research public data and maps, and draw on knowledge and experience in the area to provide the Owner with an estimate of how many unit rate mats to anticipate when constructing the Project.

A.1.31 Extra Rock Shield

Includes all labor, Equipment, materials, and fabrication required to install rock shield according to Owner's construction Specifications. The Contractor shall furnish and install when requested/approved by the Owner Representative(s). All supplies and/or consumables required to secure the rock shield to the piping shall be supplied by the Contractor. Rock shield for riser and wye blocks shall be installed per the standard typical Drawings; it shall be included in the cost of the riser/wye installation and not invoiced separately.

A.1.32 Extra Fill Dirt

Includes furnishing fill dirt free of rock that satisfies Owner Specifications for backfill. Installation of fill dirt required for pipeline backfill is within the base lay scope above.

A.1.33 Extra Gravel

Includes furnishing and installation of 1" minus crushed gravel *only in addition* to base scope. Excludes gravel furnished/installed as part of the above-ground site scope above and gas meter/LACT scope below.

A.1.34 Extra Depth

Additional depth where requested by the Owner Representative(s), except for foreign pipeline crossings and where specified by the alignment sheets or line list. Foreign pipeline crossing unit rates include extra depth required to complete the pipeline crossing.

A.1.35 Extra Mobilization & Demobilization

Only applicable when the Owner is at fault for causing the Contractor to fully demobilize from the Project Site (materials, Equipment, trailers, conexes, and personnel) and remobilize. Excludes baseline mobilization and demobilization, which is included in the base lay scope. An extra mobilization & demobilization must be approved by the Owner Representative(s); when approved, the Owner will pay the lesser of the applicable T&M rates or the quoted standby unit rate.

A.1.36 Extra Bollards

Includes all labor, Equipment, materials, and fabrication required to install and coat steel bollards per the standard typical Drawings. Excludes bollards associated with the LACT installation scope described below.

A.1.37 Line & Bore Pipe Transportation Adder

SCOPE OF WORK | CONSTRUCTION SERVICES

The Owner will typically contract stringing trucks to deliver line & bore pipe to ROW; on a Project-specific basis, the Owner will request that the Contractor coordinate and furnish these logistics. The Contractor shall provide a unit rate adder to supply transportation and logistics to deliver line and bore piping from the pipe yard below on stringing trucks to the ROW:

Line & Bore Pipe Yard Location(s)	Monahans Bulk Transfer Yard 3377 TX-18, Thorntonville, Tx 79756 .625 and .750WT Bore Pipe will be at Falcon Laydown Yard 31.9879924,- 104.0621470
--	---

A.1.38 Access Road

Includes all labor, Equipment, and materials required to install access roads per the 'High Traffic Road Section' specifications embedded in Owner's Minimum Compaction and Gravel Placement Standard Typical drawing.

Additional Access Road Clarifications	See Land Restrictions
--	-----------------------